



Project : Greater Manchester Police HQ and Divisional HQ.

Client: Carillion

Total Project Value: £77M

Subcontract Value: £7.2M

Commenced: July 2009

Duration: 135 Weeks



Scope: Greater Manchester Police commissioned a new Headquarters building consisting of predominantly offices, and a new Divisional Headquarters with both offices and custody suite. Murraywood carried out the full groundworks package.



- Excavation and construction of reinforced concrete foundations and pile caps.
- Installation of foul and surface water drainage systems and associated interceptor and rainwater harvesting tanks.
- Basement construction in both buildings measuring approximately 20m x 15m x 3m.
- Waterproofing to basement.
- 7 upper floors with concrete beam infills and soffit works with perimeter upstands and plinths.
- Over 10,000m² preparation work and asphalt surfacing to car parks.
- External stairway and pedestrianised public realm area laid to granite, with granite clad walls to match.



